

# **Specifications**

#### **Technical details**

| Overall dimensions | 4.6m L x 1.6m B x 1.3m H |
|--------------------|--------------------------|
| Weight in air      | 3.5Te                    |

## **Capability**

| Working pressure        | 280bar   |
|-------------------------|--|
| Max. line tension force | 50kN (can be increased to 70kN)                                      |
| Cable opening min.      | 0mm / Max. 250mm   |
| Speed control           | 0 -50 m/min (0 -3,000m/h)  |
| Wheel pairs             | 5x wheel pair with wheel ø 620mm/each                                |
| Wheel drive             | 10x hydraulic motors with individual gear boxes and hydraulic brakes |

#### **Power**

| HPU             | 75kW                       |
|-----------------|----------------------------|
|                 | 2.8m L x 1.1m B x 2.2m H - |
|                 | 2.4Te                      |
| Required supply | 440V, 60Hz, 3 phase        |

### Length measurement

Temporarily installed frame-mounted load cell
Hohner Encoder, HWI103S-2021R073-3600

#### **Control**

| Manual via joystick  |
|--|
| Constant speed   |
| Constant tension   |
| Wheel pairs can be opened, closed, started and stopped either simultaneously or separately |
| Operations via remote control console c/w local and remote emergency stop                  |
|  |

#### **Tension measurement**

Permanently installed frame-mounted load-cell

PAT Krüger with 0-10,000 kg capacity

